RESERVOIR COMMITTEE AGENDA ITEM 3.4 ENGINEERING FEASIBILITY APPROACH

AUGUST 21, 2020



Improved Cost Estimate Certainty

- Value planning efforts resulted in an estimated project cost savings of over \$2 Billion
- Progression of feasibility design has resulted in identification of technical data gap that may influence design assumptions and project cost estimate
- A high-level gap analysis was prepared on the focus areas that may have the greatest near-term impact on project feasibility and cost certainty



Improved Cost Estimate Certainty: Geologic and geotechnical data

Uncertainty

 Feasibility design and assumptions are currently based on limited historical geologic and geotechnical data

Implications

 Insufficient geologic and geotechnical data may misinform design approach, which affects project cost and affordability certainty

Mitigation Strategy

 Staff is coordinating with the Bureau of Reclamation for support of additional geologic and geotechnical investigations to inform and verify feasibility design



Improved Cost Estimate Certainty: Colusa Basin Drain (CBD) Feasibility

Uncertainty

- It has not been verified if the CBD can accommodate project releases of up to 1,000 cfs
- If the CBD cannot accommodate project flows, then alternative project features will need to be design and constructed for releases to the Sacramento River
- Implications
 - Difference in cost certainty between the alternatives
- Mitigation Strategy
 - The engineering team is currently preparing a hydraulic model of the CBD to verify conveyance capacity and identify potential hydraulic impacts



Improved Cost Estimate Certainty: Emergency Drawdown and Release Impacts

Uncertainty

 Regulatory requirements for emergency drawdown releases may result in localized flooding, but the extent is currently unknown

Implications

 The need for flood easements and/or impacts mitigation may increase project cost

Mitigation Strategy

- As part of upcoming Phase 2 work, the engineering team will perform a flood analysis of the release areas to determine the extent of impacts due to emergency drawdown releases
- This analysis will inform requirements for coordination with property owners to obtain flood easements and/or refine project components



Improved Cost Estimate Certainty: Power Transmission and Delivery

- Uncertainty
 - Pacific Gas & Electric (PG&E)
 - Potential transmission and power delivery provider
 - Western Area Power Administration (WAPA)
 - Can provide transmission, but no capacity for power delivery
 - There has been minimal coordination for interconnection with PG&E or WAPA facilities
- Implications
 - There is insufficient data regarding PG&E and WAPA facilities to inform design and cost estimates for project interconnection
- Mitigation Strategy
 - Staff has initiated contact with PG&E and WAPA. Next steps include submitting interconnection application with PG&E and WAPA to perform required studies that will inform facilities design and cost estimates



Improved Cost Estimate Certainty: Salt Lake

Uncertainty

- Saline water has been observed to seep from underground springs in the vicinity of the valley floor within the proposed inundation area of Sites Reservoir
 - Forms Salt Lake
 - Wetted area is seasonal and varies from 0 to 30 acres

Implications

- Mitigation measures for Salt Lake may be required for regulatory approvals
 - Affects permit ability and cost certainty
- Mitigation Strategy
 - The project team is working on identifying mitigation approaches to present for regulatory concurrence



Improved Cost Estimate Certainty: Agency Coordination and Review

- Uncertainty
 - DWR DSOD approvals
 - Geotechnical investigation work plan
 - Design criteria / dam type selection
- Implications
 - DWR DSOD concurrence of jurisdictional project features are required for project acceptance
- Mitigation Strategy
 - The engineering team will develop and execute an engagement plan with DWR DSOD as part of the upcoming Phase 2 work
 - Early engagement will assist with expediting reviews and acceptance of project features
 - Provide better assurance of cost certainty as part of early design efforts



Improved Cost Estimate Certainty

- Operations and Engineering Workgroup identified an additional consideration – material needs and source sufficiency
- Focus areas will be priority for the upcoming Phase 2 work
- A well-developed feasibility study is essential for obtaining project cost certainty and affordability

